लमही नगरपालिका
नगर कार्यपालिकाको कार्यालय
लमही, दाङ
लुम्बिनी प्रदेश, नेपाल

प.सं. २०८३/०८४

च. नं. ४४९

मिति : २०८३/०६/१३

श्री सम्बन्धित सबैको जानकारीका लागि ।

विषयः बोलपत्र सम्बन्धी सूचना ।

यस कार्यालयबाट मिति २०८३/०६/०२ गते प्रकाशित "Construction of Rihar Chyaukhola Ringroad" सम्बन्धी बोलपत्र सूचना, Contract ID: 01-LAMAHI-NCB-2083/084, अनुमानित लागत रकम रु. ४९,५४,६४१।- (VAT तथा PS बाहेक), बोलपत्र दस्तुर रु. ३,०००।- तथा बोलपत्र जमानत रकम रु. १,७०,०००।- कायम गरी बोलपत्र आह्वान गरिएकोमा उक्त सूचना राष्ट्रिय दैनिक पत्रिकामा प्रकाशन हुनुका साथै यस कार्यालय तथा नगरपालिकाको वेबसाइटमा समेत प्रकाशित भइसकेको व्यहोरा सम्बन्धित सबैको जानकारीका लागि सूचित गरिन्छ। साथै, सार्वजनिक खरिद अनुगमन कार्यालयबाट प्राप्त पत्रबमोजिम e-GP System सञ्चालनमा नआएसम्म बोलपत्रदाताले बोलपत्रसम्बन्धी कागजातहरू Mail/Hand/Courier मार्फत पेश गर्नुपर्ने व्यवस्था रहेको हुँदा, उक्त बोलपत्रका लागि आवश्यक BOQ तथा अन्य सम्बन्धित बोलपत्र कागजातहरू यसै सूचनासाथ संलग्न राखिएको व्यहोरा समेत जानकारी गराइन्छ। प्रकाशित सूचनामा उल्लेखित अन्य सम्पूर्ण शर्त, म्याद, बोलपत्र पेश गर्ने स्थान तथा समय लगायतका विवरणहरू यथावत् कायम रहनेछन्। साथै, बोलपत्रदाताहरूले संलग्न BOQ तथा बोलपत्रसम्बन्धी कागजातहरू अध्ययन गरी सूचनामा उल्लेखित शर्त तथा समयसीमाभित्र आवश्यक प्रक्रिया पूरा गरी बोलपत्र पेश गर्नुहुन सम्बन्धित सबैको जानकारीका लागि यो सूचना प्रकाशित गरिएको छ।

२०८३/०६/१३

वरिष्ठ इन्जिनियर

Lamahi Municipality
Office of the Municipal Executive
Lamahi, Dang
Lumbini Province, Nepal

BOQ

Name of the Project :- Construction of Rihar Chyaukhola Ringroad
Location :- Lamahi Municipality word no. -9, Dang

Chief Administrative Officer

FY:-2083/084

S.No.	Descriptions of Work	Unit	Quantity	Rate in Numeric Form	Rate in Alphabetical Form	Total Amount (Quantity * Rate)	Remarks
A	**General Works**						
1	Provide, operate and maintain Quality control laboratory including equipment,accessories and consumables for both field testing facilities and off-site test with manpower as per Contract Documents as per specification (SS/SP-502,511) and instruction of engineer.	**PS**	1	50,000.00	Fifty Thousand only	50,000.00	
2	Relocation of public utilities/servises and repairing for exiting infrastructures as instructed by engineer	**LS**	1	20,000.00	Twenty Thousand only	20,000.00	
3	Insurance for the loss of damage to works, plant,material, equipment property and personnel injury or death, including third party insurance as per Contract Document (SS/SP- 117)	**PS**	1	20,000.00	Twenty Thousand only	20,000.00	
				Sub-Total A	**Ninety Thousand only**	**90,000.00**	
B	**Pavement Work**						
1	Scarifying the existing road surface to a depth of 50 mm and disposal of scarified Material with in all lifts and lead as per Drawing and Technical Specifications by mechanical meansup to 30m lead (Spec. cl. No: 1003)	**sq.m**	3378.00				
2	Loosening of the ground upto a level of 500mm below the sub-grade level , watering, graded and compacted in layers as per Drawing and Technical Specification (compacting orginal ground supporting sub-grade)	**cu.m**	337.80				

3	Providing and laying granular sub-base on prepared surface, mixing at OMC, and compacting to achieve the desired density, complete as per Drawing and Technical Specifications by mechanical means(Spec. cl. No: 1201)	**cu.m**	349.06				
4	Providing and laying Crusher Run Macadam on a prepared surface, spreading and mixing, watering and compacting to form a layer of base course as per Drawing and technical Specifications.	**cu.m**	523.59				
5	Providing and Applying Prime coat with hot bitumen (including Cutter) of grade VG 30 on the prepared surface of granular base including cleaning of road surface and spraying at specified rate by mechanical means as per the Technical Specification.	**Ltr.**	3040.20				
6	Providing and Applying Tack coat with hot paving grade VG 30 bitumen by mechanical means at specified rate on the prepared surface including cleaning as per the Technical Specification.	**Ltr.**	1689.00				
7	Providing and laying open-graded premix carpet of 20 mm thickness composed of 13.2 mm to 5.6 mm aggregates as wearing course on a previously prepared base as per drawing and Technical Specifications by manual means(Spec. cl. No: 1311)	**cu.m**	67.56				
8	Providing and laying seal coat sealing the voids in a bituminous surface as per Drawing and Technical Specifications (Spec. cl. No: 1310)	**sq.m**	3378.00				
				Sub-Total B			
	Total Bid Amount (A)						
	VAT @ 13% (B = 13% *A)						
	PS Item (C)						
	Grand Total (A+B+C+D)						

Chief Administrative Officer

Lamahi Municipality
Office of the Municipality Executive
Lamahi, Dang
Lumbini Province, Nepal